

## **TECHNICAL SPECIFICATIONS**

### **1. SCOPE OF WORK**

The scope of work under this contract shall include transportation and disposal of anaerobically digested dewatered sludge (biosolids) at a permitted sludge (biosolids) disposal facility from the biosolids dewatering facility of Lower Bucks County Joint Municipal Authority's (Authority) Wastewater Treatment Plant located at 7900 Bristol Pike, Levittown, Bucks County, Pennsylvania. The Contractor shall furnish all labor, materials, and equipment required for collection, transportation, and disposal of the dewatered biosolids at a permitted sludge disposal facility from the Authority's Wastewater Treatment Plant. The Contractor shall also provide required dumpster(s) for the collection of dewatered biosolid cake from the dewatered biosolids conveyor installed to transport dewatered biosolids from biosolids dewatering centrifuge. The Contractor is expected to visit the job site prior to his/her bid to verify the exact conditions and dimensions at the facility. At least one (1) spare empty dumpster shall always be kept at the Authority's Wastewater Treatment Plant.

### **2. LOCATION OF BIOSOLIDS DEWATERING FACILITY**

The biosolids dewatering facility is located at the Authority's Wastewater Treatment Plant located at 7900 Bristol Pike, Levittown, Bristol Township, Bucks County, Pennsylvania.